

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 45W

C-1

T R

T 46N R 45W

C-13

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section corner, sec's 5, 6, 31 & 32; T.45-46 N., R.45 W.

I, Richard L. Drahn in a field survey on May 3, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt in August, 1847. Original B.T.s --- 10" Hemlock N.65 E. 25 links (16.50') --- W. Pine 24" N.31 W. 34 links (22.44') --- Spruce 14" S.52 E. 17 links (11.22') --- Y. Birch 10" S.58 W. 20 links (13.21') ---

Bill Stuth, Wisc. RLS recovered the remains of the W. Pine, still scribed in 1984. R. Drahn (21564) and J. Goss (23509), on 11/13/84, recovered the remains of the first three B.T.s and the stump hole of the fourth. The W. Pine B.T. stump was still scribed. At the corner they set a 2" X 30" alum. pipe with a 3 1/2" stamped alum. cap and the following new B.T.s: --- 13" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16") N.20 W. (N.20 W.) 19.55' (19.44' new nail) --- 8" (9") Twin red Maple S.42 E. (S.43 E.) 28.33' (28.32') --- 12" (15") Cedar S.62 W. (S.63 W.) 26.45' (26.38 new nail) --- 6' Steel sign rail North 2.6' (2.55').---

They recorded the corner in Liber 2, Page 613-614 of Gogebic County Corner Records on 12/6/84.

Corner position found marked by the monument as described and the 1984 B.T.s as indicated in parentheses above. The remains of the 1847 B.T.s are still evident although the scribing is no longer evident on the W. Pine.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.

6" Black Cherry N.87 E. 22.53 feet.

PEER GROUP APPROVED
Richard L. Drahn 5/12/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date May 8, 1997

Surveyor's Michigan License No. 21564

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3	6	5	4										
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register's Office }
Gogebic County } ss.
Received for record the
13th day of MAY
A. D. 1997 at 1:55 o'clock
P. M., and recorded in
Liber 6 of CORNERS
on page 107
Ramona Coccine, Deputy
Register of Deeds

Register of Deeds Stamp & File Number