

AUG 08 1997

COMM.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
13th day of MAY
A. D. 1997 at 1:55 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 108
Kamona Collins, Deputy
Register of Deeds

For corners in
Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>45W</u>	E-1
	T <u>46N</u> R <u>45W</u>	E-13
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Section Corner, sec's 4, 5, 32 & 33; T.45-46 N., R.45 W.

I, Richard L. Drahn in a field survey on May 3, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by John Burt, in August 1847. Original B.T.s --- 22" Y. Birch N.50 E. 31 links (20.46') --- Hemlock 24" N.28 W. 27 links (17.82') --- Lynn 12" S.33 W. 15 links (9.90') --- Sugar 14" S.13 E. 32 lks. (21.12')

Bill Stuth, Wisc. RLS, in 1984 recovered the remains of the Y. Birch and the Hemlock B.T.s. On 11/13/84, R. Drahn (21564) and J. Goss (23509) recovered the same decayed remains and the stump hole of the Lynn B.T. They set a 2" X 30" alum. monument with a 3 1/4" stamped aluminum cap and new B.T.s --- 6" Sugar Maple (6" broken stub) S.37 E. (S.36 E.) 4.40' (4.32') --- 12" (13") Sugar Maple N.16 E. (N.21 E.) 20.57' (20.31' new nail) --- 10" Sugar Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
N.67 W. (N.64 W.) 21.95 (21.97') --- 6' Steel sign rail N.10 W. (N.09 W.) 2.0' ---


Corner recorded in Gogebic County records in Liber 2, Page 611 on 12/6/84.
Corner position found marked by the monument as described and the 1984 B.T.s as indicated in parentheses above. The remains of the first three 1847 B.T.s are still evident.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established a new B.T.:
9" Sugar Maple S.04 E. 28.07'

PEER GROUP APPROVED
Richard L. Drahn 5/12/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date May 9, 1997
Surveyor's Michigan License No. 21564