

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>45W</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 21, 22, 27 & 28; T.46 N., R.45 W

I, Richard L. Drahn in a field survey on November 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/2/1851. Original B.T.s --- Y. Birch 24" S.73 W. 45 links (29.70') --- Cedar 12" N.33 E. 49 links (32.34') --- 1960 State Hiway Plans indicate the corner marked by a 1½" iron pipe. New B.T.s set in 1960: --- 4" Maple N.40 W. 8.78' --- 8" Maple South 11.01' --- 6" Maple N.25 E. 10.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner position found marked by a 1½" iron pipe with a 2¼" brass cap by NORTHERN PAPER MILLS stamped 21, 22, 27, & 28. (No name or date) at record bearing and distance from the decayed remains of the original Y. Birch bearing tree. No evidence remains of the original Cedar B.T.

Recovered the States 1960 B.T.s as: 7" Sugar Maple with MSHD brass washer N.40 W. 8.78'; 15" Sugar Maple South 11.01'; 11" Sugar Maple N.29 E. 10.92'.

4" scribed Cedar post bears N.11 W. 0.5'.

PEER GROUP APPROVED
Richard L. Drahn 11/11/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the location of the brass capped iron pipe I set a 2" dia. by 30" long aluminum monument with a 3¼" alum. cap stamped: COUNTY REMONUMENTATION; T.46 N., R.45 W.; S-21, S-22, S-27, S-28; 1996; RLS 21564; 1996. I blazed and scribed and placed B.T. tags on the MSHD B.T.s.

New bearing object referenced:

6' Steel sign rail S.60 E. 2.16'

Signed by Richard L. Drahn Date November 11, 1996
 Surveyor's Michigan License No. 21564

Register's Office }
 Gogebic County } sa.
 Received for record the
9TH day of APRIL
 A. D. 1997 at 10:45 o'clock
A m., and recorded in
Libr 6 of CORNERS
 on page 46
Richard J. Brown
 Register of Deeds *cc*

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

