

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
9th day of APRIL
 A. D. 1997 at 10:45 o'clock
A m., and recorded in
 Lib. 6 of CORNERS
 on page 97
Richard L. Brown
 Register of Deeds CR

Register of Deeds Stamp & File Number

For corners in
Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>45W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 27, 28, 33 & 34: T.46 N., R.45 W.

I, Richard L. Drahn in a field survey on November 4, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/2/1851. Original B.T.s --- Sugar 10" S.58 E. 12 links (7.92') --- Sugar 8" N.53 W. 20 links (13.20') ---

1960 State Hiway Plans indicate the corner marked by a 4" squared post. New B.T.s set in 1960: --- 5" Birch S.35 W. 17.75' --- 3" Birch S.85 E. 7.40' --- 6" Maple N.10 W. 16.55' ---

William Stuth, Wisc. RLS found corner marked by an iron pipe and a wood post in 1984.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original bearing trees destroyed by logging and road construction. Corner position found marked by a 2 1/4" X 2.6' iron pipe. Recovered the States 1960 B.T.s as: dead and down Y. Birch bearing S.46 W. app. 17.8', recover the brass MSHD washer --- no evidence remains of the Birch at S.85 E. --- 11" live Sugar Maple with 1960 brass MSHD washer at N.10 W., 16.55'

Scribed 3" sq. Cedar post bears S.46 E. 0.6'

3/4" dia. iron pipe bears S.08 E. 0.5'

Due to this corners long usage I accepted its' location as best representing the point set by Austin Burt in 1851.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the location of the 2 1/4" iron pipe I set a 2" dia by 30" long aluminum monument with a 3 1/4" Alum. cap stamped: COUNTY REMONUMENTATION, T.46 N., R.45 W.: S-27, S-28, S-33, S-34: RLS 21564: 1996. From which I set the following new B.T.s ---

- | | | | |
|-----|-----------------|---------|--------|
| 6' | Steel sign rail | N.57 W. | 1.74' |
| 9" | Sugar Maple | N.15 E. | 20.66' |
| 8" | Sugar Maple | S.07 E. | 37.89' |
| 10" | Sugar Maple | S.65 W. | 36.18' |

PEER GROUP APPROVED
Richard L. Drahn 11/11/96
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date November 8, 1996

Surveyor's Michigan License No. 21564