

SURVEY & REMONUMENTATION
APR 07 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
21ST day of OCTOBER
 A. D. 1994 at 11:15 o'clock
A m., and recorded in
 Liber 5 of CORSE
 on page 144
Ramona Collins Deputy
 Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>45W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Section Corner 25, 26, 35, & 36, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I Richard L. Drahn in a field survey on October 10, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt Deputy Surveyor on July 30, 1851.
 Original bearing trees: Y. Birch 16" S.42 E. 21 links (13.86 ft.)
 Y. Birch 14" N.11 W. 13 links (8.58 ft.)

R.G. Campbell & R. Lunn, timber cruisers, on 8/23/35, recovered the SE BT as a 20" scribed yellow birch. They placed a location poster on the NW side of the BT from which the corner lay NW 5 feet.

Corner research form on file at Gogebic County Register of Deeds Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position from the cut stump remains of the SE BT. The NW BT has been destroyed by road construction and logging operations. a 2½" iron pipe bears S.42 E., 0.9 feet and appears to have been measured from the center of the decayed birch stump rather than from the location of the measuring notch. A 6" scribed cedar post bears S.27 E., 1.2 feet; a very old 3" squared cedar post lays on ground at corner location. Distance east to recovered section corner is in accordance with the field notes of the original Government survey.

PEER GROUP Approved

Richard L. Drahn 10/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" by 30" aluminum monument with a 3¼" aluminum cap, stamped to read: COUNTY REMONUMENTATION; T.46 N., R.45 W.; S. 25, S. 26, S. 35, S. 36; 1994; R.L.S. 21564. From which I established the following new blazed and scribed bearing trees.

9"	Sugar Maple	S.60 E.	13.23 feet
7"	Sugar Maple	S.06 W.	7.14 feet
5"	Sugar Maple	S.65 W.	26.67 feet
6'	Steel sign rail	N.13 W.	1.65 feet



Signed by Richard L. Drahn

Date October 11, 1994

Surveyor's Michigan License No. 21564