

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of MAY
A. D. 1998 at 3:10 o'clock
1 m., and recorded in
Liber 6 of CORNERS
on page 348
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

SECTION

For corners in

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>44W</u>	<u>A-4</u>
	T <u>46N</u> R <u>45W</u>	<u>M-54</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 7 & 12, T.46 N., R.44-45 W

Richard L. Drahn in a field survey on April 11, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- Hemlock 30" S.35 E. 26 links (17.16') --- Hemlock 12" N.35 W. 45 links (29.70') ---

Corner restored by Richard L. Drahn, 21564, on 5/11/83 from the remains of the two original B.T.s, and recovered line trees north and south. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{2}$ " stamped aluminum pipe and the following:

9"	Sugar Maple	N.36 W.	18.61'
7"	White Ash	N.59 E.	32.19'
8"	Sugar Maple	S.20 W.	21.14'
6'	Steel sign rail	N.81 E.	1.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County, Liber 2, Page 533 on 1/26/84.

Corner research on file with Gogebic County records.

A stump hole with fragments of hemlock wood and bark are all that remain of the original SE bearing tree, and a stump hole remains of the NW B.T.

Recovered the monument as described and the bearing trees as follows:

12"	Sugar Maple	N.36 W.	18.80 (new nail)
9"	White Ash	N.58 E.	32.19' " "
10"	Sugar Maple	S.18 W.	21.13'
6'	Steel sign rail	N.80 E.	1.77'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

9" Sugar Maple S.88 W. 12.69'

NEER GROUP APPROVED
Richard L. Drahn 5/13/98
CHIEF SURVEYOR



Signed by Richard L. Drahn Date April 12, 1998
Surveyor's Michigan License No. 21564