

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 44W A-5
T 46N R 45W M-5
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register's Office
Gogebic County

Received for record the
14TH day of MAY
A. D. 1998 at 3:10 o'clock
9 m., and recorded in
Liber 6 of CORNERS
on page 349
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 7, 18, 12 & 13; T.46 N., R.44-45 W.

I, Richard L. Drahn in a field survey on April 11, 1998, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s: --- Cedar 16" S.65 W. 18 links (11.88') --- Cedar 10" N.20 E. 13 links (8.58') --- B. Ash 8" S.50 E. 17 links (11.22') --- Hemlock 6" N.65 W. 29 links (19.14') ---

In 1935, Campbell and Linn recovered scribing on both Cedars and the Hemlock B.T. and placed a location poster on the Black Ash bearing tree.

Richard L. Drahn (21564), on 5/9/83 restored the corner location from the remains of all four bearing trees. 1935 tag recovered on the Black Ash B.T. He set a 3/4" X 6' solid aluminum rod with a 3 1/4" stamped aluminum cap and the following:

13" Hemlock N.37 E. 58.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7" Yellow Birch N.81 E. 32.88'

12" Hemlock S.83 W. 21.70'

6" Steel sign rail N.82 E. 1.4'

Corner recorded in Gogebic County, Liber 2, Page 535 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the 1983 B.T.s as follows:

13" Hemlock N.33 E. 58.77' (new nail)

9" Yellow Birch N.81 E. 32.74'

13" Hemlock S.85 W. windthrown and near dead

6' Steel sign rail N.85 E. 1.57'

Recovered remains of all four original B.T.s and the 1935 location poster.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

9" White Spruce N.73 W. 58.28'

12" Cedar N.31 W. 47.35'

PEER GROUP APPROVAL

Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date April 12, 1998

Surveyor's Michigan License No. 21564