

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>th</sup> day of JUNE  
A. D. 1998 at 1:20 o'clock  
9 m., and recorded in  
Liber 7 of CORNER  
on page 2  
Ronald Collins, D.D.  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 44W	A-6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 Corner, 18 & 130; T.46 N., R.44-45 W.

I, Richard L. Drahn in a field survey on June 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- Y. Birch 18" S.32 W. 27 links (17.82') --- Y. Birch 30" N.82 E. 44 links (29.04') ---

Corner restored by Richard L. Drahn (21564) on 5/25/83, from the remains of the two original B.T.s. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

10"	Sugar Maple	N.28 W.	25.47'
7"	Sugar Maple	N.67 E.	50.32'
17"	Hemlock	S.10 E.	58.92'
6'	Steel sign rail	S.87 E.	2.4'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County in Liber 2, Page 537 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

13"	Sugar Maple	N.30 W.	25.47' (new nail)
10"	Sugar Maple	N.66 E.	50.33' " "
20"	Hemlock	S.15 E.	58.92' " "
6'	Steel sign rail	S.89 E.	2.36'

Badly decayed Yellow Birch stumps still remain from the original B.T.s.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree referenced:

11"	Sugar Maple	S.75 W.	17.18'
-----	-------------	---------	--------

PEER GROUP APPROVAL  
Richard L. Drahn 6/11/98  
GOGEBIC COUNTY REGISTER



Signed by Richard L. Drahn Date June 11, 1998

Surveyor's Michigan License No. 21564