

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

For corners in **SECTION**
Gogebic
 (County)

Received for record the
18th day of JUNE
 A. D. 1998 at 1:25 o'clock
P m., and recorded in
 Liber 7 of CORNERS
 on page 3
Ramona L. Collins, Dep.
 Register of Deeds

	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>44W</u>	<u>A-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u>46N</u> R <u>45W</u>	<u>M-7</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 18, 19, 13 & 24; T.46 N., R. 43-44 W.

I, Richard L. Drahn in a field survey on June 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												●
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/30/1847. Original B.T.s --- Tamarack 10" S.42 E. 22 links (14.52') --- Tamarack 10" N.53 W. 48 links (31.68') --- Tamarack 6" S.43 W. 56 links (36.96') --- Tamarack 6" N.29 55 links (36.3')
 Corner restored by Richard L. Drahn (21564) on 4/16/83 at the point of the original Spruce point and at record bearing and distance from the remains of all four of the original B.T.s which were still scribed.
 He set a 3/4" X 9' solid aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s:

- 3" Tamarack N.69 W. 45.23'
- 4" Black Spruce N.36 E. 12.11'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 3" Tamarack S.27 W. 49.81'
- 6' Steel sign rail N.81 E. 1.35'

Corner recorded in Gogebic County in Liber 2, Page 539 on 1/26/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- 5" Tamarack N.69 W. 45.22'
- 5" Black Spruce N.35 E. 12.12'
- 5" Tamarack S.26 W. 49.76'
- 6' Steel sign rail N.86 E. 1.38'

Evidence of all four original B.T.s still remain, with the B.T. at S.42 E. still a standing stub with scribing visible.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 5" Black Spruce S.66 E. 13.65'

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
 COUNTY REGISTRAR



Signed by Richard L. Drahn Date June 11, 1998

Surveyor's Michigan License No. 21564