

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

Register's Office }
Gogebic County } ss.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. R. 44 X. W.	A-10
2. PROPERTY CONTROLLING IN SECTION _____	T. 46 N. R. 45 X. W.	M-10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Received for record the
5TH day of January
A. D. 1994 at 10:05 o'clock
A m., and recorded in
Liber 4 of CORNERS
on page 350
Betty Lavin Deputy
Register of Deeds

REGISTER OF DEEDS STAMP AND
FILING NUMBER

Quarter corner 30 & 25, T46N, R44-45W.

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 10 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on August 30, 1847.
Original bearing trees:

Hemlock	20"	S.86°E.	20 links	(13.20 feet)
Hemlock	14"	N.26°W.	30 links	(19.80 feet)

17.09 chains south Y. Birch 18" line tree
15.11 chains north Y. Birch 20" line tree

No record of subsequent corner restoration found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Restored corner position at record bearing and distance from the remains of the two original hemlock bearing trees. Both B.T. stumps are decayed to well below ground level. The line tree 17.09 chains south of the corner is now a decayed 24-28" yellow birch stump. The line tree 15.11 north of the corner is now a 36" live yellow birch. Corner position lays within 1 foot of a mathematical analysis of the range line between ranges 44 and 45 west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2 1/2" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap, stamped to read: T46N, R44-45-W; 1/4; S-30, S-25; 1993; R.L.S. 21564. From which I have established the following new blazed and scribed bearing trees:

10"	Red Maple	N.44°E.	13.98 feet	
14"	Hemlock	S.23°E.	7.48 feet	
13"	Hemlock	S.74°W.	11.01 feet	
6'	Steel rail	S.50°W.	2.02 feet	

PEER GROUP APPROVED

Richard L. Drahn 1/20/94

SIGNED BY _____ COUNTY REPRESENTATIVE DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Richard L. Drahn DATE December 20, 1993
MICHIGAN REGISTERED LAND SURVEYOR



FED T-1

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564