

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
30<sup>th</sup> day of OCTOBER  
A. D. 1998 at 9:05 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 67  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	
SECTION 12	<del>T46N</del> R 47W		M-5
	<u>T46N</u> R 46W		<u>A-5</u>
2. Property Controlling in Section	S	T	R
3. Miscellaneous	S	T	R
Property in Sec.	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION CORNER TO 12, 13, 7 & 18, T46W, R46-47W

JOHN R GARSKE

I, \_\_\_\_\_, in a field survey on OCT. 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY WILLIAM BURT, D.S. 1847.  
ORIGINAL CORNER: CEDAR POST  
ORIGINAL BEARING TREES:  
CEDAR 8" S60°W 20 LINKS  
TAMARACK 18" N38°E 7 LINKS

PEER GROUP RE-EVALUATED  
Richard P. Deahn 10/27/98  
COUNTY REGISTER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I SEARCHED AT THE INTERSECTION OF NIEMI AND SOUTH DAVIS ROADS WITH NOTHING FOUND. DISTANCES FROM KNOWN CORNERS NORTH AND SOUTH, PLACE THE CORNER APPROXIMATELY 33 FEET SOUTH OF THE INTERSECTION. THE GOGEBIC COUNTY ROAD COMMISSION HAS NO INFORMATION ON THE CORNER OR RIGHT OF WAY ON NIEMI ROAD. NATURAL FEATURE TIES DID NOT HELP TO POSITION THE CORNER. I SET THE CORNER BY SINGLE PROPORTIONAL MEASUREMENT IN THE CENTER OF THE ROAD, BETWEEN KNOWN CORNERS IN ACCORDANCE WITH THE ORIGINAL GOVERNMENT NOTES, SEE SKETCH ON BACK.

(RESEARCH ON FILE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I SET A 3 1/4" DIA. BRASS CAP ON A 5/8" X 12" IRON ROD, STAMPED TO IDENTIFY THE CORNER, FROM WHICH I ESTABLISHED:  
18" SPRUCE S88°W 55.15 FEET  
U.S.G.S. BENCH MARK N59°E 43.32 FEET  
A" BALSAM S55°E 37.00 FEET  
REFERENCE MONUMENT 2 1/2" X 30" ALUMINUM PIPE MONUMENT WITH A 3 1/4" DIA. ALUMINUM CAP (STAMPED) EAST 24.00 FEET  
STEEL SIGN RAIL EAST 1.02 FEET FROM R.M.

Signed by John R Garske  
Surveyor's Michigan License No. 28410

Date 10-26-98



T 47 N

FENCE LINE ——— 12 7 ——— EAST END ROAD

1/4 COR.  
R 47 W R 46 W

SURVEY &  
REMONUMENTATION

DEC 15 1998

SECTION

N 00° 47' 14" E  
2634.80' (M)  
2640.00' (R-GLO)

WHITNEY CREEK  
SOUTH DAVIS ROAD

NIEMI ROAD  
35°  
12 7  
13 18

RANGE LINE

N 00° 03' 10" W  
2634.82' (M)  
2640.00' (R-GLO)

BERGSLEIN ROAD ——— 13 18 ——— TRAIL  
1/4 COR.

SOUTH DAVIS ROAD

