

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T46 N R46 W. E-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
MONUMENTATION**

JAN 05 2001

**SECTION**

Register's Office }  
Gogebic County } ss.

Received for record the  
22<sup>ND</sup> day of JUNE  
A. D. 1800 at 1:20 o'clock  
7 m., and recorded in  
Book 7 of CORNERS

Page 393  
*Cheryl Ruppel Rep.*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 28, 29, 32 & 33; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 7/9/1851. Original bearing trees:  
Hemlock 8" S.28° W. 26 links (17.16')  
Sugar 10" N.18° E. 16 links (10.56')

C. Haight, in 1935, recovered a scribed 18" Hemlock witness tree. He set a location poster on the north side of a 14" Hemlock and indicated the B.T. is 10' (no bearing). Tag also on R.R. 15 chains south.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large windthrown depression. The second one is now a very badly decayed 16-20" offsite Sugar Maple. The witness tree recovered by Haight in 1935 and his tag tree have both been destroyed by logging activity. The location poster 15 chains south has been destroyed by road construction.

A very old 3/4" X 4 1/2" iron pipe, nearly rusted off at ground line bears S.41° E., 16.7'. The pipe appears to have been set facing the original witness tree. Haight's records indicate that it lay in section 33.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4" aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Sugar Maple	10"	N.42° W.	16.30'
Black Ash	7"	S.65° E.	18.11'
Black Ash	11"	S.27° W.	28.59'
Steel sign rail	6"	N.18° W.	2.33'

**DEED GROUP APPROVED**  
*Richard L. Drahn 6/21/00*  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 14, 2000  
Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1963  
REVISED OCT., 1986