

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
22nd day of JUNE
 A. D. 1900 at 1:20 o'clock
P m., and recorded in
 Liber 7 of CORNERS
 on page 394

Cheryl Rupp, Dep.
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic Located In: Corner Code #
 (County)

1. Public Land Survey T46 N R46 W. E-12
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
 MONUMENTATION**
 JAN 05 2001
 SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner 32 & 33; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 7/9/1851. Original bearing trees:

Fir	10"	S.27° E.	33 links	(21.78')
Hemlock	10"	N.38° W.	25 link	(16.50')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the original Hemlock bearing tree. It is now a very badly decayed Hemlock stump with Hemlock roots, bark and wood. This is the only old growth hemlock remains recovered at this latitude. No evidence remains of the original Fir bearing tree.

A maple picket with blazed and painted and/or ribboned lines running north, south and west; bears S.80° E., 64 feet from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Red Maple	7"	N.40° E.	6.46'
Red Maple	6"	S.26° W.	32.27'
Sugar Maple	5"	S.63° E.	30.04'
Steel sign rail	6'	N.72° W.	1.92'

Richard L. Drahn 6/21/00
 BEER GROUP APPROVED
 COUNTY REGISTERED



Signed by Richard L. Drahn Date June 14, 2000
 Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 REVISED OCT., 1995