

SURVEY & REMONUMENTATION

JAN 22 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
24th day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 269.
Ramona Collins Deputy
Register of Deeds

For corners in _____
Gogebic
(County)

Located In:	Corner Code #		
Section 33	47W	46W	G-13
	46W	46W	G-1
	T	R	
	T	R	
	T	R	
	T	R	
	T	R	
	T	R	
	T	R	
	T	R	

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claim corner to 33, 34, 3 & 4, T47-46N, R46W

I, John R. Garske, in a field survey on November 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1847. Original corner was a cedar post from which:
 W. Pine 22" N66°E 11 links-(7.26')
 Spruce 7" N57°W 9 links-(5.94')
 W. Pine 36" S80°W 36 links-(23.76')
 Spruce 6" S30°E 25 links-(16.5')
 Ledge top of knob 2 ch's East, 0.25 ch's north - descend ledge, 2.5 ch's south descend hill.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found ~~a fence~~ an ancient barbwire fence running east and north. At this location someone painted an "x" on a large flat rock. This position lines up well with the roads running north and south. It also checks very well with the GLO calls north 0.25 chains, south 2.50 chains to descend hill and 2 chains east to top of ledge. The fence line picks up again on the west side of Johnson Road. I set the corner at this position based on the fence and GLO ties.

(Research on file)

PEER GROUP APPROVED

Richard L. Dean 11/11/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:
 5" Balsam S7°W 15.74 feet
 6" Cedar S87°E 14.96 feet
 5" Balsam N10°W 12.15 feet
 Steel Sign Rail S82°W 1.31 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/11/97

