

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T46 N R46 W. G-11  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R SURVEY &  
3. Miscellaneous S T R MONUMENTATION  
Property in Sec. S T R  
JAN 05 2001

Received for record the  
27<sup>TH</sup> day of JULY  
A. D. 2000 at 10:50 o'clock  
A m., and recorded in  
Liber B of CORNERS  
pg. 9  
Richard L. Drahn  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat SECTION  
5. Private Claims \_\_\_\_\_

Section Corner 27, 28, 33 & 34; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on July 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8											
5													
6	18	17											
7													
8	19	20											
9													
10	30	29											
11													
12	31	32											
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 7/7/1851. Original bearing trees:

Aspen	5"	S.20 3/4° E.	58 links	(38.28')
Sugar	12"	N.20 1/2° W.	1.49 chains	(98.34')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the stump holes of the two original bearing trees, at record distance east from "Ledge, 20 ft., 50 links north of line, SSW" and record distance north of "Stream 20 links, NW". The 5.10 chain distance West from corner to "Stream, 20 links, NW" checks to an old stream bed.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Black Cherry	11"	S.47° E.	19.15'
Sugar Maple	7"	S.34° W.	29.32'
Red Maple	16"	N.31° E.	10.09'
Steel sign rail	6'	N.55° W.	1.99'

**FIELD GROUP APPROVED**  
Richard L. Drahn 7/20/00  
COLLECTOR



Signed by Richard L. Drahn Date July 16, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983