

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
22<sup>ND</sup> day of JUNE  
 A. D. 2000 at 1:20 o'clock  
P m., and recorded in  
 Book 7 of CORNERS

page 396  
*Cheryl Ruppe, Reg.*  
 Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46</u> N R <u>46</u> W.	<u>H-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	<u>SURVEY &amp; MONUMENTATION</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	<u>JAN 05 2001</u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Quarter Corner 27 & 34; T.46 N. R.46 W.

I, Richard L. Drahn, in a field survey on June 21, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 7/8/1851. Original bearing trees:

Cedar	8"	S.06° E.	12 links	(7.92')
Tamarack	16"	N.22° W.	21 links	(13.86')

Wm. Brash, on 6/25/35 found a squared Cedar post at this location. He placed a location poster on the NW side of a 14" spruce, corner lay south 12 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a badly decayed 18-24" Tamarack stump, the only old growth Tamarack remains recovered within a 40' radius. The second one is now a shallow windthrown stump hole. A 5" squared Cedar post bears S.53° W., 5.3 feet from the original corner location. Unable to locate the 1935 location poster or tag tree.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 8 ft. aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Cedar	10"	N.43° W.	4.40'
Cedar	12"	N.77° E.	13.07'
Cedar	9"	S.25° E.	8.95'
Steel sign rail	6'	S.38° W.	1.72'



*Richard L. Drahn* 6/21/00  
 COUNTY DEPARTMENT

Signed by Richard L. Drahn Date June 21, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 REVISED OCT., 1985