

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Saginaw County } ss.

For corners in

Gogebic Located In: Corner Code #
 (County)

1. Public Land Survey T46 N R46 W. I-12
 T R
 T R SURVEY &
 T R REMONUMENTATION

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

SECTION

Received for record the
22nd day of JUNE
 A. D. 2000 at 1:20 o'clock
P m., and recorded in
 Liber 7 of CORNERS
 on page 397
Richard L. Drahn, Reg.
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner 34 & 35; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 21, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/27/1851. Original bearing trees:

Cedar	10"	S.65° W.	23 links	(15.18')
Y. Birch	10"	N.26° E.	20 links	(13.20')

L. Chautelois, on 5/28/35, found a squared stake at this location. He placed a location poster on the east side of a 5' Black Ash from which the post lay 9 links west and 50 links north.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original corner location was found marked by a very old, (not original), Cedar post at record bearing and distance from the windthrown stump holes of the original bearing trees. Post lays within 2 feet north and south of the GPS positioned corner location. Unable to locate the 1935 location poster or tag tree.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 8 ft. aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Yellow Birch	9"	S.10° W.	15.43'
Cedar	12"	N.52° E.	20.07'
Black Ash	7"	N.46° W.	5.76'
Steel sign rail	6'	S.45° E.	2.24'



DEED GROUP APPROVED
Richard L. Drahn 6/21/00
 COUNTY REGISTERED

Signed by Richard L. Drahn Date June 21, 2000
 Surveyor's Michigan License No. 21564