

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
21ST day of JULY
A. D. 1999 at 1:05 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 176
Ramona Collins, Deputy
Register of Deeds

For corners in SECTION

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>46W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>46N</u> R <u>46W</u>	<u>I-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 2, 3, 34 & 35; T.45-46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/31/1847. Original bearing trees:

Spruce	12"	N.80° E.	80 links	(52.80')
Spruce	8"	N.36° W.	36 links	(23.76')
Spruce	14"	S.49° W.	38 links	(25.08')
Spruce	12"	S.11° E.	43 links	(28.38')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the original bearing trees. Corner area is in a large open swamp grass meadow. As mature trees die and fall over they provide a solid base for tag alder clumps to take root on. The only alder clumps observed in the area are on these downed trees. No evidence of the original Spruce wood remains, only a clump of alder that had taken root on them. Also observed was an absents of grass hummocks where the trees root system had been uplifted. The 0.50 chain distance east to "Brook 2 lks. SW", the 2.10 chain distance south to "Stream 2 lks. SW" and the 1.50 chain distance west to "Leave swamp, N&S" are all in accord with the field notes of the original Government survey.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' long solid aluminum rod with a 3 1/4" stamped aluminum cap and the following new bearing objects.

Steel sign rail	6'	N.02° E.	6.99'
Steel sign rail	6'	N.89° E.	9.63'
Steel sign rail	6'	S.01° W.	6.43'
Steel sign rail	6'	S.89° W.	8.57'

PEER GROUP APPROVED

Richard L. Drahn 7/20/99
COUNTY PROFESSIONAL SURVEYOR



Signed by Richard L. Drahn Date June 13, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976