

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T46 N R46 W.

J-11

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

SURVEY &
MONUMENTATION

JAN 05 2001

SECTION

Received for record the
27th day of JULY
A. D. 1900 at 10:50 o'clock
A m., and recorded in
8 of CORNERS

on page 10
Cheryl R. [Signature]
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner 26 & 35; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11										●			
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/30/1851. Original bearing trees:

Cedar	10"	S.20° E.	6 links	(3.96')
Hemlock	20'	N.05° W.	18 links	(11.88')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a 14-16" badly decayed, downed Cedar with portions of reversed scribing and measuring notch still visible. The second one is now a very large, badly decayed Hemlock stump. Portions of the major roots and Hemlock bark is all that remains.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" x 48" aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Yellow Birch	10"	N.80° E.	11.85'
Hemlock	7"	S.07° W.	7.50'
Hemlock	13"	N.37° W.	35.72'
Steel sign rail	6'	S.66° W.	1.90'

PEER GROUP APPROVED
Richard L. Drahn 7/26/00
CORNER SURVEYOR



Signed by Richard L. Drahn Date July 1, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

REVISED OCT., 1995