

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T 45N R 46W J-1  
T R  
T R  
T 46N R 46W J-13

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

Received for record the  
21<sup>st</sup> day of JULY  
A. D. 1999 at 1:15 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
on page 178  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner 2 & 35; T.45-46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1									●			
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13									●			

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/31/1847. Original bearing trees:  
Hemlock 12" N.45 E. 3 links (1.98')  
Hemlock 14" N.17 W. 45 links (29.70')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the two original B.T.s. The first is a 16-20" Hemlock stump, decayed to near ground level. The second one in now a large deep stump hole with small portions of the major Hemlock roots and Hemlock knots.

A Cedar post and an iron pipe set by Gogebic County Forestry Commission bears N.40 W., 25.9 feet from the original corner location.


Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s:

Sugar Maple 8" N.74 W. 24.08'  
Red Maple 6" S.27 E. 25.39'  
Sugar Maple 5" N.09 W. 23.50'  
Steel sign rail 6' N.14 E. 2.72'

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTERED



Signed by Richard L. Drahn Date July 13, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1978  
REVISED JAN., 1983