

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

SECTION

For corners in

Received for record the
10TH day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 154
Pamela Collins, Deputy
Register of Deeds

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T45N R46W</u>	<u>K-1</u>
	T <u> </u> R <u> </u>	
	T <u> </u> R <u> </u>	
	<u>T46N R46W</u>	<u>K-13</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 1, 2, 35 & 36; T.45-46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/31/1847. Original bearing trees:

Hemlock	16"	N.11° E.	29 links (19.14')
Cedar	6"	N.77° W.	48 links (31.68')
Cedar	10"	S.20° W.	24 links (15.84')
Hemlock	14"	S.81° E.	18 links (11.88')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the following original B.T.s:

- Stump hole with fragments of Hemlock bark at N.11° E. 19.1'
- Series of root holes with fragments of Cedar wood at N.77° W. 31.7'
- Windthrown stump hole with portions of Cedar wood downwind at S.20° W. 15.8'
- 18-24" decayed Hemlock stump with portions of B.T. blaze overgrowth at S.81° E. 11.9'

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 3' long aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s:

Cedar	15"	N.75° E.	36.75'
Cedar	14"	S.35° W.	35.66'
Hemlock	6"	N.76° W.	49.75'
Steel sign rail	6'	S.23° W.	1.87'

DEED GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REGISTER



Signed by Richard L. Drahn Date June 5, 1999

Surveyor's Michigan License No. 21564
USFS A-21

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986