

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }  
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>46W.</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the  
10<sup>TH</sup> day of NOVEMBER  
A. D. 1999 at 11:25 o'clock  
A m., and recorded in  
Liber 7 of CORNERS

on page 267  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner 24 & 25; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on November 5 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/30/1851. Original bearing trees:  
Y. Birch 12" S.16° W. 26 links (17.16')  
Hemlock 24" N.53° E. 22 links (14.52')

Leo Chauletois on 7/25/35 recovered a scribed 16" Yellow Birch B.T. laying south 19 links from a wood post. He placed a location poster on the north side of the bearing tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original B.T.s. The first is a 20-30" badly decayed Yellow Birch stump and a four foot portion of the first log. I recovered portions of the badly rusted 1935 location poster on the log. The second B.T. is now a large Hemlock decayed to well below ground line. I recovered portions of a 3" squared picket 5 feet SW of the original corner position.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Yellow Birch	10"	S.79° W.	18.25'
Yellow Birch	9"	N.04° W.	12.43'
Yellow Birch	6"	S.64° E.	24.23'
Steel sign rail	6'	N.05° W.	1.97'

PEER GROUP APPROVED  
Richard L. Drahn 11/9/99  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date November 7, 1999

Surveyor's Michigan License No. 21564  
USFS R-23

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN. 1983

REVISED OCT., 1996