

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
 Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46 N R46 W.	L-11
	T ___ R ___	
	T ___ R ___	SURVEY &
	T ___ R ___	MONUMENTATION
2. Property Controlling in Section	S ___ T ___ R ___	JAN 05 2001
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	SECTION

Received for record the
22nd day of JUNE
 A. D. 2000 at 1:20 o'clock
P m., and recorded in
 Liber 7 of CORNERS
 on page 398
Cheryl Krupp, Dep
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter corner 25 & 36; T.46 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 15, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/30/1851. Original corner; Hemlock 8".
 Original bearing tree: Cedar 8' South 17 links (11.22')

G. Kongstaed on 7/8/35, recovered a Hemlock post at this corner; no scribing found. He placed a location poster on a 16" soft maple from which the post lay east, 135 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at the center of the original Hemlock corner tree. It is now a very badly decayed Hemlock stump as evidenced by Hemlock roots, bark and portions of the Hemlock log under 6" of swamp litter. This is the only old growth Hemlock remains recovered in a 35 foot radius. The original bearing tree is now shallow depression bearing south 11.2 feet from the original corner location.

Unable to locate G. Kongstaeds' 1935 location poster or tag tree.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 48" aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Yellow Birch	8"	N.47° W.	3.02'
Black Ash	6"	N.71° E.	22.81'
Black Ash	6"	S.18° E.	14.49'
Steel sign rail	6'	S.04° E.	2.12'

PEER GROUP APPROVED
Richard L. Drahn 6/21/00
 COUNTY REGULATOR



Signed by Richard L. Drahn Date June 20, 2000

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1996