

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
30th day of OCTOBER
A. D. 1998 at 9:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 64.
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 46N R 45W _____ A-2
T _____ R _____
T _____ R _____
46N R 46W _____ M-2

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Quarter Corner 6 & 1; T.46 N., R.45-46 W.

I, Richard L. Drahn in a field survey on October 2, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/1/1847. Original B.T.s --- Hemlock 10" S.19 W. 15 links (9.90') --- Y. Birch 30" N.40 E. 5 links (3.30') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large windthrown stump hole with Hemlock root and bark fragments. (The only old growth Hemlock remains within a 30' radius.) The second one is now a widespread series of very large root holes with fragments of Yellow Birch bark.

Corner research on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 10/27/98
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects:

- 10" Yellow Birch S.02 E. 8.24'
- 6" Twin Sugar Maple S.88 W. 8.42'
- 8" Yellow Birch N.47 E. 21.55'
- 6' Steel sign rail S.87 E. 2.29'

A 3/4" iron pipe and guard post bears N.15 E. 27.5'.



Signed by Richard L. Drahn Date October 6, 1998

Surveyor's Michigan License No. 21564