

JAN 05 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } 33.

For corners in

Gogebic County	Located in:	Corner Code #
1. Public Land Survey	T46N R47W	K-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Received for record the
22ND day of JUNE
A. D. 19 at 1:20 o'clock
P m., and recorded in
liber 7 of CORNERS
page 399
Chester Rupp, Dep.
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on November 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-4) 1/4 Corner Common to Sections 11 & 12, T46N, R47W

1848 - William Ives set 1/4 post with ties:

10" Hemlock	N 20°W	23 links
8" Fir	S 23°E	36 links

I found no record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. North - South Van Buskirk Road now runs over area of corner. I created a position for the 1/4 corner at the intersection of centerline of Van Buskirk Road and the extension of a very old fence to the West. This position works well with section corners to the North and South. After consulting John Garske, P.S., who has done extensive remonumentation work in this area, I accepted this position as the true 1/4 corner position.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" iron pin with a 3" diameter bronze cap stamped to read: COUNTY REMONUMENTATION: T46N, R47W; 1/4; S. 11, S. 12; 1999; P.S. 37273. A reference monument was also set to the Northeast, a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to indicate that the 1/4 corner is S 50°W, 42.79'. Corner falls in centerline of Road, 32' North of a driveway. Ties to the Corner:

R.M.	N 50°E	42.79' (1.36' further to Steel Sign Rail)
10" Twin Soft Maple	S 86°E	43.19'
12" Hemlock	S 35°W	64.98'
8" Soft Maple	N 30°W	65.78'

Richard L. Walsh 6/21/00
COUNTY REPRESENTATIVE

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by John C. Domitrovich

Date 6/21/00

Surveyor's Michigan License No. 37273