

JAN 05 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
 Gogebic County } ss.

For corners in

Gogebic County	Located in:	Corner Code #
1. Public Land Survey	T46N R47W	L - 3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Received for record the
22nd day of June
 A. D. 19th 00 at 1:20 o'clock
9 m., and recorded in
 Liber 7 of CORNERS
 on page 400
Cheryl Ruppe, Dep.
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on November 11, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-3) 1/4 Corner Common to Sections 1 & 12, T46N, R47W.

1848 - William Ives set a 1/4 post with ties:

14" Tamarack	S 06°W	11 links
6" Tamarack	N 38°W	48 links

I found no record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. East - West Puumala Road now runs over 1/4 corner position. I re-established the 1/4 corner at the intersection of centerline Puumala Road on the extension of fence line to South. This position works well with distances to Section Corners east and west but falls 24.2' south of a straight line between them. I believe this corner best represents the true 1/4 corner position and after consulting John Garske, P.S., who has done extensive remonumentation work in this area, I have accepted it.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" iron pin with a 3" diameter bronze cap stamped to read: COUNTY REMONUMENTATION; T46N, R47W; 1/4; S. 1, S. 12; 1999; P.S. 37273. A reference monument (R.M.) was also established to the NE, a 3/4" x 48" aluminum rod with a 3" diameter aluminum cap stamped to indicate that the 1/4 corner is S 43°W, 35.28'. Corner falls 1.5' west of culvert crossing. Ties:

R.M.	N 43°E	35.28' (1.31' further to steel sign rail)
7" Cedar	S 70°E	93.06'
8" Cedar	S 48°E	52.19'
Corner Fence Post	S 01°E	38.26'

DEER GROUP APPROVED
Richard H. Dralun
 COUNTY REMONUMENTATION

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by John C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 6/25/00