

**JAN 05 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office } ss.  
Gogebic County }

For corners in

Gogebic County Located in: Corner Code #

1. Public Land Survey T46N R47W L - 5  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R  
S T R  
S T R

4. Lot No. , Recorded Plat

5. Private Claims

Received for record this  
22<sup>nd</sup> day of JUNE  
A. D. 19<sup>00</sup> at 1:20 o'clock  
P m., and recorded in  
liber 8 of CORNERS

on page 1  
Cheryl Ruppe, Dep.  
Register of Deeds

Register of Deeds Stamp & File Number

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Joseph C. Domitrovich, in a field survey on November 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

(L - 5) ¼ Corner Common to Sections 12 & 13, T46N, R47W.

1848 - William Ives set ¼ post with ties:

10" Yellow Birch S 58°E 13 links  
15" Yellow Birch N 29°W 18 links

I found no record of subsequent restoration.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. East - West Niemi Road now runs over area of ¼ corner. I created a position for the ¼ corner at an even split of the distance between section corners and on centerline of Niemi Road. After consulting John Garske, P.S., who has done extensive remonumentation work in this township, I have accepted this position as the ¼ corner.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" iron pin with a 3" diameter bronze cap stamped to read: COUNTY REMONUMENTATION; T46N, R47W; ¼; S. 12, S. 13; P.S. 37273; 1999. A reference monument (R.M.) was also established to the NW, a ¼" x 48" aluminum rod with a 3" diameter aluminum cap stamped to indicate that the ¼ corner is S 37°E, 36.62'. Corner falls 2.5' east of culvert crossing. Ties:

R.M. N 37°W 36.62' (1.46' further to steel sign rail)  
8" Balsam N 72°E 58.34'  
6" Cherry S 58°E 54.70'  
16" Red Pine S 62°W 54.20'

DEER GROUP APPROVED  
Richard P. Orphan 6/21/00  
SOURCE REPRESENTATIVE

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 6/21/00

Surveyor's Michigan License No. 37273