

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
16 day of SEPT
 A. D. 1994 at 4:10 o'clock
P m., and recorded in
 Liber 5 of CORNER
 on page 141
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in			
<u>Gogebic</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>47N</u> R <u>47W</u>	<u>M-13</u>	
	T _____ R _____	_____	
	T <u>47N</u> R <u>46W</u>	<u>A-13</u>	
	T _____ R _____	_____	
2. Property Controlling	S _____ T <u>46N</u> R <u>47W</u>	<u>M-1</u>	
in Section	S _____ T _____ R _____	_____	
3. Miscellaneous	S _____ T <u>46N</u> R <u>46W</u>	<u>A-1</u>	
Property in Sec.	S _____ T _____ R _____	_____	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Township corner common to Sections 36, 31, 1 & 6, T47-46N,
 R47-46W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

June 20 94
 I, John R. Garske, in a field survey on _____, 19_____,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

On September 3, 1847, William A. Burt set a hemlock post at town corner from which a Y. Birch
 16" bears S25°E, 25 links and a hemlock 18" bears S52°W, 21 links.

No original evidence found due to road construction.

PEER GROUP **Approved**
Richard E. Dralin 9/14/94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 2' long x 2" diameter pointed iron pipe 4" below road surface. Pipe was found to be bent
 and in poor condition. I carefully dug up corner and replaced it at the mark the point of the pipe
 left in our excavation. I accepted the corner as being true due to the substantial pipe found, at the
 proper location within the intersection of South Davis and East Pioneer Road. This pipe has been
 used and accepted as the section corner for many years.

After restoring the corner position, I upgraded it as noted below to state and county specifications.
 Corner was found 0.50 feet west of the approximate centerline of South Davis Road and 1.50 feet
 north of the approximate centerline of East Pioneer Road.

Research record form on file with County Register of Deeds Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced found bent iron pipe with a 1" x 36" iron pipe with a 2 1/2" brass cap with a 2" stem on
 top of pipe set in anchoring cement 3" below road surface. I established the following bearing
 trees and reference objects: A reference monument consisting of a 2 1/2" x 30" aluminum pipe
 with a 3 1/4" aluminum cap stamped to indicate the corner position as follows: S47°E, 48.12 feet
 with a steel sign post 1.71 feet away; 14" R. pine - N20°E, 108.44 feet; P. pole #5 - S45°E,
 39.82 feet; P. pole #1 - 94/93 - S52°W, 41.87 feet.

Signed by John R. Garske Date 8/31/94
 Surveyor's Michigan License No. 28410

