

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
30th day of OCTOBER
A. D. 1998 at 9:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 67
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC
(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	
SECTION 12	<u>R6N</u>	<u>R 47W</u>	<u>M-5</u>
	<u>T46N</u>	<u>R 46W</u>	<u>A-5</u>
2. Property Controlling in Section	S	T	R
3. Miscellaneous Property in Sec.	S	T	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION CORNER TO 12, 13, 7 & 18, T46W, R46-47W

I, JOHN R GARSKE, in a field survey on OCT. 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY WILLIAM BURT, D.S. 1847.
ORIGINAL CORNER: CEDAR POST
ORIGINAL BEARING TREES:
CEDAR 8" S60°W 20 LINKS
TAMARACK 18" N38°E 7 LINKS

PEER GROUP APPROVED
Richard L. Deak 10/27/98
COUNTY REGISTER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I SEARCHED AT THE INTERSECTION OF NIEMI AND SOUTH DAVIS ROADS WITH NOTHING FOUND. DISTANCES FROM KNOWN CORNERS NORTH AND SOUTH, PLACE THE CORNER APPROXIMATELY 33 FEET SOUTH OF THE INTERSECTION. THE GOGEBIC COUNTY ROAD COMMISSION HAS NO INFORMATION ON THE CORNER OR RIGHT OF WAY ON NIEMI ROAD. NATURAL FEATURE TIES DID NOT HELP TO POSITION THE CORNER. I SET THE CORNER BY SINGLE PROPORTIONAL MEASUREMENT IN THE CENTER OF THE ROAD, BETWEEN KNOWN CORNERS IN ACCORDANCE WITH THE ORIGINAL GOVERNMENT NOTES, SEE SKETCH ON BACK.

(RESEARCH ON FILE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I SET A 3 1/4" DIA. BRASS CAP ON A 5/8" X 12" IRON ROD, STAMPED TO IDENTIFY THE CORNER, FROM WHICH I ESTABLISHED:
18" SPRUCE S88°W 55.15 FEET
U.S.G.S. BENCH MARK N59°E 43.32 FEET
A" BALSAM S55°E 37.00 FEET
REFERENCE MONUMENT 2 1/2" X 30" ALUMINUM PIPE MONUMENT WITH A 3 1/4" DIA. ALUMINUM CAP (STAMPED) EAST 24.00 FEET
STEEL SIGN RAIL EAST 1.02 FEET FROM R.M.

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 10-26-98



T 47 N

FENCE LINE ——— 12 7 ——— EAST END ROAD
1/4 COR.

R 47 W

R 46 W

N 00° 47' 14" E
2634.80' (M)
2640.00' (R-GL0)

WHITNEY CREEK

SOUTH DAVIS ROAD

SURVEY &
RECONSTRUCTION

DEC 15 1998

SECTION

NIEMI ROAD ——— 12 7 ———
33' ———
13 18

RANGE LINE

N 00° 03' 10" W
2634.82' (M)
2640.00' (R-GL0)



BERGSLEIN ROAD ——— 13 18 ——— TRAIL
1/4 COR.

SOUTH DAVIS ROAD

