

DEC 15 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
 Gogebic County }

Received for record the
30th day of OCTOBER
 A. D. 1998 at 9:05 o'clock
A m., and recorded in
 Liber 7 of CORNER
 on page 68.
Ramona Collins, Deputy
 Register of Deeds

For corners in

GOGEBIC Located In: Corner Code #
 (County)

1. Public Land Survey
 SECTION 24 T R
46N R 47W M-9
46N R 46W A-9

2. Property Controlling in Section S T R
 S T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SECTION CORNER TO 24, 25, 19 & 30, T46N, R46-47W

I, JOHN R GARSKE, in a field survey on OCT. 21, 98
19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL TOWNSHIP SURVEY BY WILLIAM BURT, D.S. 1847.
 ORIGINAL CORNER: B. ASH POST
 ORIGINAL BEARING TREES:
 Y. BIRCH 18" N80°W 15 LINKS
 SPRUCE 14" S53°E 20 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THE CORNER FALLS IN THE CENTER OF SOUTH DAVIS ROAD AND NO INFORMATION COULD BE FOUND IN THE PROXIMITY OF THE CORNER. I ESTABLISHED THE CORNER BY SINGLE PROPORTIONAL MEASUREMENT ON THE RANGE LINE IN ACCORDANCE WITH THE ORIGINAL GOVERNMENT NOTES BETWEEN KNOWN CORNER POSITIONS AS SHOWN ON THE SKETCH ON THE BACK.

(RESEARCH ON FILE)

PEER GROUP REVIEWED
Richard J. Walsh 10/27/98
 COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I SET A 3 1/4" DIA. BRASS CAP STAMPED TO IDENTIFY THE CORNER ON A 12" X 5/8" DIA. IRON ROD AT THE CORNER POSITION BURIED 2" BELOW THE GRAVEL SURFACE OF SOUTH DAVIS RD. FROM WHICH:
 P. POLE S45°W 41.78 FEET
 10" SPRUCE N47°W 63.00 feet
 4" CEDAR S73°E 44.95 FEET
 REFERENCE MONUMENT CONSISTING OF A 2 1/2" ALUMINUM PIPE MONUMENT WITH A 3 1/4" DIA. STAMPED ALUMINUM CAP:
 WEST 47.00 FEET
 STEEL SIGN RAIL WEST 1.40 FEET FROM R.M.

Signed by John R Garske
 Surveyor's Michigan License No. 28410

Date 10-26-98



T 46 N

SIIRILA ROAD

MAKI ROAD

R 47 W

R 46 W

MONUMENTED CORNER

SOUTH DAVIS ROAD

SURVEY & REINFORCEMENT

DEC 15 1998

SECTION

RANGE LINE

N 00° 10' 17" E
2641.97' (M)
2640.00' (R-GLO)

N 00° 10' 17" E
2641.97' (M)
2640.00' (R-GLO)

N 00° 10' 17" E
2641.98'
2640.00' (R-GLO)

25 30
36 31
MONUMENTED
RECORDED
CORNER

24 19
25 30
SET BY
SINGLE PROPORTION

25 30
1/4 COR.
SET BY SINGLE
PROPORTION

