

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record this  
12<sup>th</sup> day of APRIL  
 A. D. 1995 at 2:00 o'clock  
P M., and recorded in  
 Liber 5 of CORNERS  
 on page 250  
Barbara Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in  
Gogebic & Ontonagon  
 (County)

Located in:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>48N</u> R <u>42W</u> | <u>B-13</u> |
|                                    | T <u>47N</u> R <u>42W</u> | <u>B-1</u>  |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

N 1/4 Cor of Sec. 6, T.47 N., R.42 W.  
 S 1/4 Cor of Sec. 31, T.48 N., R.42 W

1. John P. Goss, in a field survey on March 26, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

| A  | B  | C  | D  | E  | F  | G  | H  | I  | J  | K  | L  | M  |
|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 2  | 6  | 5  | 4  | 3  | 2  |    |    |    |    |    |    |    |
| 3  |    |    |    |    |    |    |    |    |    |    |    |    |
| 4  | 7  | 6  | 5  | 4  | 3  | 2  | 1  |    |    |    |    |    |
| 5  |    |    |    |    |    |    |    |    |    |    |    |    |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 | 12 | 11 | 10 | 9  | 8  | 7  |
| 7  |    |    |    |    |    |    |    |    |    |    |    |    |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 |
| 9  |    |    |    |    |    |    |    |    |    |    |    |    |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | 24 | 23 | 22 | 21 | 20 | 19 |
| 11 |    |    |    |    |    |    |    |    |    |    |    |    |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |    |    |    |    |    |    |
| 13 |    |    |    |    |    |    |    |    |    |    |    |    |

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Wm. A. Burt on August 10, 1848. Set a Hemlock Post. Original Bearing Trees; Hemlock 16"- N 27°W-45 links; Lynn 14"- N 38°E-14 links.

John P. Goss in 1983 using MDOT witnesses set a 1 inch iron rebar and recorded this corner in Liber 2 pages 308 and 309 of Gogebic County Land Corners; 8" Maple- N 60°E- 11.28'; 4" Maple- S 40°W- 13.78'; 9" Maple- N 29°W- 33.46'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 1 inch iron rebar marking the corner position and it checked with witnesses in John P. Goss certificate. I updated the corner monument and accessories as noted below to state and county specifications.


Act 74 research on file with the County Register of Deeds Office.

PEER GROUP APPROVED  
Richard H. Deakin 4/6/95  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Over the 1 inch iron rebar I set a 2 1/2" x 30" aluminum pipe with a 3/4" aluminum cap stamped: County Remonumentation; 1/4; S-6; S-31; T.47-48 N.; R.42 W.; 1995; P.S. 23509. I established the following bearing trees and reference objects.

|                                 |        |        |
|---------------------------------|--------|--------|
| D.H. Nail & Tag in 10" Maple    | N 60°E | 11.28' |
| D.H. Nail & Tag in 6" Maple     | S 40°W | 13.78' |
| D.H. Nail & Tag in 12" Maple    | N 24°W | 33.66' |
| D.H. Nail & Tag in 16" Basswood | S 76°E | 18.81' |
| Steel Sign Post                 | N 80°W | 1.21'  |



Signed by John P. Goss  
 Surveyor's Michigan License No. P.S. 23509

Date March 30, 1995