

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>X</u> , R. <u>42</u> E. <u>W</u> .	B-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____	PEER GROUP Approved	
5. PRIVATE CLAIMS _____	<u>Richard P. Drahn</u> <u>1/20/92</u>	
Quarter corner 30 & 31; T.47N., R.42W.		

Register's Office }
Gogebic County } sa.

Received for record the
4TH day of JANUARY
A. D. 1992 at 2:00 o'clock
P m., and recorded in
Liber 4 of CORNER
page 200
Richard J. Brown
Register of Deeds

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on November 4 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Original corner established by Algernon Merryweather, U.S. Deputy Surveyor, on July 7, 1851; original bearing trees:
- | | | | | |
|--------|-----|----------------------|----------|--------------|
| Cedar | 12" | S.45 ⁰ W. | 14 links | (9.24 feet) |
| Balsam | 8" | N.37 ⁰ E. | 41 links | (27.06 feet) |


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No evidence of original corner bearing trees or subsequent corner restoration found. Corner position re-established by single proportionate methods on line between the Northeast and Northwest section corners of Section 31; T.47N., R.42W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- At the corner position I set a 3/4" outside diameter by 4' long aluminum rod monument with a 3" cast aluminum cap, stamped to read: T.47N., R.42W.; 1/4; S-30, S-31; 1992; R.L.S. 21564; from which I have established the following new blazed and scribed bearing trees:
- | | | |
|----------------|----------------------|------------|
| 9" Sugar Maple | N.10 ⁰ E. | 10.45 feet |
| 6" Sugar Maple | S.75 ⁰ W. | 19.20 feet |
| 7" Sugar Maple | S.64 ⁰ E. | 7.49 feet |
| 6' Steel rail | S.31 ⁰ E. | 2.1 feet |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Richard L. Drahn DATE 12-28-92
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

U.S.F.S. V-3 (SEAL)