

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

Register's Office }
Gogebic County } ss.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. 8., R. 42 W. X.	D-1
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>47</u> N. <u>42</u> E. W.	D-13
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		
Quarter Corner _____ 5 & 32 _____	T. 46-47 N., R. 42W.	

Received for record the
4TH day of JANUARY
A. D. 1992 at 2:00 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 196
Richard J. Brown Jr
Register of Deeds

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 4 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by William Burt, U.S. Deputy Surveyor, in 1847.
Original bearing trees:

Sugar	10"	N.50°E.	11 links	(7.26 feet)
Sugar	5"	N.21°W.	11 links	(7.26 feet)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
No evidence found of original corner, bearing trees or subsequent corner restoration.
Corner position re-established by single proportionate methods between the north quarter corner of section 6 and the northwest section corner of section 4; T.46N., R.42W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position, I set a standard 2½" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap, Stamped to read: T.46-47N., R.42W.; ¼; S-5, S-32; 1992; R.L.S. 21564.

From which I have established the following new blazed and scribed bearing trees:

9"	Sugar Maple	N.15°E.	23.30 feet	
12"	Hemlock	S.06°E.	28.40 feet	
9"	Sugar Maple	S.68°W.	3.51 feet	
6'	Steel rail	N.15°E.	2.3 feet	

PEER GROUP APPROVED

Richard L. Drahn 4/7/94
COUNTY REPRESENTATIVE

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Richard L. Drahn DATE 12-28-92
MICHIGAN REGISTERED LAND SURVEYOR

U.S.F.S. #A-7

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564