

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. <del>X</del> , R. 42 <del>X</del> W.	E-11
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. _____ S. _____, R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. _____ S. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS		

Register's Office }  
Gogebic County } ss.

Received for record the  
4<sup>th</sup> day of JANUARY  
A. D. 1993 at 2:10 o'clock  
9 m., and recorded in  
Liber 4 of CORNERS  
on page 203.  
Richard J. Brown for  
Register of Deeds

**PEER GROUP**

**Approved**

Richard L. Drahn 1/20/94

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

Section corner 28, 29, 32 & 33; T.47N., R.42W.

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 26 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by Algernon Merryweather, U.S. Deputy Surveyor, on July 5, 1851; original bearing trees:

Sugar	11"	N.80°E.	16 links	(10.56 feet)
Sugar	9"	S.43°W.	15 links	(9.90 feet)

Thomas Dental, timber cruiser, on 03/09/35 recovered a scribed 20" Sugar Maple at this location.

On September 8, 1977, I recovered fragments of original scribing on a 22" Sugar Maple Witness Tree on the South side of a logging road

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Original bearing trees destroyed by logging road. Original Witness recovered in 1977 has been cut and the stump moved into stump dump 150 feet westerly. Stump hole of Witness Tree still evident. Corner position restored by proportionate measure East and West and record distance from recovered corner South. Location is consistent with record natural features North, South and West; Witness Tree location was S.10°W., 15.5 feet.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position and 6" below surface of logging road, I set a 2" I.D. by one foot long, concrete filled, galvanized iron pipe, capped with a 3" circular brass table which reads: T.47N., R.42W.; S-28, S-29, S-32; 1992; R.L.S. 21564; from which I established the following new blazed and scribed bearing trees:

8"	Yellow Birch	N.35°W.	32.70 feet
7"	Sugar Maple	S.80°E.	47.25 feet
12"	Basswood	S.10°W.	39.18 feet
30"	Reference Monument bears South 15.42 feet		
6'	Metal sign post bears South 16.43 feet		

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Richard L. Drahn DATE 12-28-92

U.S.F.S. V-9



SURVEYOR'S MICHIGAN REGISTRATION NO. 21564