

Survey &
REMONUMENTATION

APR 05 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon/Gogebic
(County)

Located In:

Corner Code 44

1. Public Land Survey	<u>Ontonagon</u>	T 48N	R 42W	F-13
	<u>Gogebic</u>	T 47N	R 42W	F-1 ✓
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register's Office }
Gogebic County } ss.

Received for record the
6th day of DECEMBER
A. D. 1994 at 10:00 o'clock
A m., and recorded in
Liber 5 of CORNER
on page 166
Barbara Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter corner common to Section 33, T48N, R42W and Section 4, T47N, R42W.

I, John R. Garske, in a field survey on October 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Survey by John and Wm. Burt in 1847. Set a cedar post from which a 7" cedar bears N81°E, 9 links and a 12" cedar - N31°W, 14 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 4" x 4" square post with scribing. Post found in standing water. Also found a cedar bearing tree with tag N88°W, 5.0 feet.

Established the corner by single proportionatal measurement, using the found meander corner and found section corner as noted on plat of Lake Gogebic East Shores recorded in 1964. The corner position is approxitely 0.8' south of the found wooden post.

Corner record research on file.

PEER GROUP

Approved

Richard L. Dralun

11/30/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I updated the corner position to state and county specifications by setting a 1-4 foot section of 3/4" aluminum swamp rod with a 3/4" aluminum cap stamped: County Remonumentation; 1/4; S-33; S-4; T48N, T47N, R42W; 1994; RLS 28410. I established the following bearing trees and reference objects: 3" ash - N33°E, 5.28 feet; 6" balsam fir - N42°W, 19.90 feet; 8" ash - S42°W, 18.04 feet; 6 foot steel rail with sign - S54°E, 1.85 feet.

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/5/94

