

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. 8., R. 42 W.	F-1
2. PROPERTY CONTROLLING IN SECTION	T. 47 N. S., R. 42 E. W.	F-13
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS Quarter Corner 4 & 33	T. 46-47 N., R. 42 W.	

Register's Office }
Gogebic County } ss.

Received for record the
4th day of JANUARY
A. D. 1993 at 2:00 o'clock
P m., and recorded in
Liber 4 of CORNWALL
on page 197
Richard L. Drahn
Register of Deeds
REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 12 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by William Burt, U.S. Deputy Surveyor in 1847.
Original bearing trees:

Sugar	8"	N. 61° E.	20 links	(13.20 feet)
Hemlock	12"	N. 72° W.	34 links	(22.44 feet)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
No evidence of original corner, bearing trees or subsequent corner restoration found. Corner re-established on line between and equal distance from the northeast and northwest section corners of Section 4, T.46N., R.42W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position, I set a 3/4" outside diameter by 3' long aluminum rod monument with a 3" cast aluminum cap, stamped to read: T.46-47N., R.42W.; 1/4; S-4, S-33; 1992; R.L.S. 21564.

From which I have established the following new blazed and scribed bearing trees:

6"	Sugar Maple	N. 37° W.	2.25 feet
7"	Sugar Maple	S. 67° E.	15.44 feet
11"	N. Red Oak	S. 37° W.	22.98 feet
6'	Steel rail	N. 39° E.	1.6 feet

PEER GROUP APPROVED

Richard L. Drahn 4/7/94

SIGNED BY _____ COUNTY REPRESENTATIVE DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Richard L. Drahn DATE 12-28-92
MICHIGAN REGISTERED LAND SURVEYOR

U.S.F.S. #A-11

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564