

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in
Gogebic
 (County)

Located In: _____ Corner Code # _____

Received for record the
16th day of DECEMBER
 A. D. 1993 at 2:25 o'clock
P m., and recorded in
 Liber 4 of CORNERS
 on page 294
Betty L. Davis Deputy
 Register of Deeds

- | | | |
|------------------------------------|---------------------------|----------------|
| 1. Public Land Survey Section 3 | T <u>47N</u> R <u>42W</u> | <u>H-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | <u>Seg. #1</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter corner S-3 & S-10, T47N, R42W.

November 29, 1993

I, John R. Garske, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Survey by Algemon Meriweather, July 2, 1851. Set one-quarter post from which a 24" hemlock bears S50°W, 10 links and a 20" hemlock bears N65°E, 25 links. No evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found one-half inch rebar with plastic cap, RLS #17610. I accepted this corner as being the one-quarter corner as it is tied into many surveys of record in the area by several surveyors.

*NOTE: SEE LIBER 6,
 PAGE 133 FOR CORRECTED
 BEARING TREE INFORMATION
 R.S.D. 6/11/97*

PEER GROUP APPROVED
Richard L. Orahn 1/20/94
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced found rebar with 3/4" x 30" rebar and 3 1/2" aluminum Bernsten cap stamped: County Remonumentation; T47N, R42W; S-3; S-10; 1/4 cor.; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 8" hemlock - N08°E - 28.64 feet
- 8" S. maple - N43°W - 39.59 feet
- 8" S. maple - S28°E - 14.86 feet
- Steel sign post - SW'ly - 1.85 feet - 3/4" iron pipe 3± high - NW'ly - 0.5 feet



Signed by *John R. Garske* Date 12-9-93
 Surveyor's Michigan License No. 28410