

**SURVEY & REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
Gogebic (County)		
1. Public Land Survey	T <u>47N</u> R <u>42W</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
7<sup>TH</sup> day of APRIL  
A. D. 1997 at 10:05 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 94  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner common to Sections 2, 3, 10 and 11, T47N, R42W.

I, John R. Garske, in a field survey on November 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- In 1848 Algernon Merryweather, U.S.D.S., set a post from which a 10" sugar bears N70°E - 17 links and a 10" sugar - S35°W - 32 links.
- 10-11-61, Neal Spherhake, R.L.S., restored corner position from found original evidence - Set a 1" diameter x 36" long galvanized iron pipe with a 4" diameter cast aluminum cap stamped to indicate corner position - 12" sugar - S46°E - 31 links; 11" sugar - N40°W - 30 links; 14" sugar - S45°W - 68 links.
- August 30, 1968 - Donald D. Lappala found Spherhake corner as noted above and established the following bearing trees: 5" sugar - S28°E - 19.7 feet; 3" sugar - S42°W - 17.3 feet, recorded in Land Corner Record Liber 1, page 89-90.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" diameter galvanized iron pipe with a 4" diameter cast aluminum cap as noted above. I updated the corner position to state and county specifications as noted below.


(P.A. 74 research on file)

PEER GROUP APPROVED  
Richard L. Deahn 11/11/96  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

The corner position is marked by a 1" diameter x 36" long galvanized iron pipe with a 4" diameter cast aluminum cap as noted above. Established the following bearing trees and reference object:

- 14" maple (existing) - S47°E - 28.32 feet
- 8" maple (existing) - S27°E - 19.59 feet
- 6" maple (existing) - S41°W - 17.25 feet
- 4" maple - N12°W - 6.54 feet
- 6' steel rail with sign - east - 2.00 feet



Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 11-11-96  
FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983