

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T47^N R42^W

I-5

2. Property Controlling
in Section

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

S

T R

Received for record the

12 day of MAY

A. D. 1999 at 10:30 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 142.

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section corner, 10, 11, 14 & 15, T.47 N., R.42 W.

I, John P. Goss, in a field survey on May 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by A. Merryweather, U.S. Deputy Surveyor, on June 29, 1851.
Original bearing trees: 7" Cedar N 58° W 15 links
12" Y. Birch S 30° E 28 links

On Nov. 1, 1961, Neal Spherhake, set a 1" iron pipe with 4" cap from the original bearing tree. He recorded said corner on page 40 in Register of Deeds Office for Gogebic County.

On June 25, 1974, Donald D. Lappala, found corner marked by 1" iron pipe and cap. Which checked with original bearing trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Lappal recorded said corner in U.S.F.S. Liber J-17 on March 4, 1975 in Register of Deeds Office for Gogebic County. He established following bearing trees:

9" Cedar N 18° W 25.6 ft.
4" Sugar Maple (dead) S 76° E 16.7 ft.
6" Sugar Maple S 38° E 32.6 ft.

FREE GROUP ATTORNEY
Richard R. Dean 5/11/99
COUNTY REGISTER

I updated the monument and accessories as noted below to state and county specification.
Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found 1" galvanizes iron pipe with 4" Aluminum cap stamped to read: Kimberly-Clark Corp. T47N 10, 11, 14, 15 R42W Spherhake RLS 7876 11-1-61. I established the following new and existing reference objects:

13" Cedar N 18° W 25.25 ft.
9" Yellow Birch S 38° E 32.88 ft.
6" Ash S 74° W 8.89 ft.
6' Metal sign post S 81° E 2.06 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss

Surveyor's Michigan License No. 23509

Date May 10, 1999.

U.S.F.S. No. J-17