

SURVEY &
REMONUMENTATION

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|----|-------|------------|-------|------------|-------------|
| 1. Public Land Survey Section | 35 | T | <u>47N</u> | R | <u>42W</u> | <u>I-13</u> |
| | | T | _____ | R | _____ | _____ |
| | | T | _____ | R | _____ | _____ |
| | | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner common to S-34, 35, 3 & 2, T47N, R42W

June 22

92

I, John R. Garske, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt, U.S.D.S., August 9, 1848. Set cedar post from which a 10" hemlock bears N52°E, 15 links and a 14" lynn (basswood) bears N52°W, 56 links. No evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" solid iron rod at corner position - found 14" maple blazed - S35°W - 16.05 feet; 8" ash - N40°W - 7.50 feet and a 1/2" iron rod capped RLS 17610 - due west - 7.15 feet. The iron rod as found has been used and accepted in several surveys of record for over 30 years.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On November 4, 1993, replaced found 1 1/2" solid iron rod with a standard aluminum County Monument - cap is stamped: County Remonumentation; T47N, R42W; S-34; S-35; S-3; S-2; T46N; 1993; RLS 28410. T46N; Established the following bearing trees and/or reference objects:

- 14" maple - S35°W - 16.05 feet
- 8" ash - N40°W - 7.50 feet
- 2" maple - S50°E - 4.62 feet
- Steel sign post - NE'ly - 1.42 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/9/93

Register's Office }
Gogebic County } ss.

Received for record the
16TH day of DECEMBER
A. D. 1993 at 2:25 o'clock
9 m., and recorded in
Liber 4 of CORNERS
on page 295
Betty Sanni Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

