

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
7TH day of NOVEMBER
 A. D. 1995 at 1:15 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 301.
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey Sections 23, 24, 25, 26	T <u>47N</u> R <u>42W</u> T _____ R _____ T _____ R _____ T _____ R _____	<u>K-9</u> _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John R. Garske, in a field survey on November 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- By A. Merriweather, June 1851 - Set wood post from which a 12" hemlock bears S36°E - 14 links and a 7" balsam - N19°W - 32 links.
- 1970's wood stake set by Champion International, Inc.
- November 1990 survey by J.R. Garske - Reestablished corner position as recorded in Liber 4, page 37. The corner set consisted of a 2" x 30" iron pipe with a 4" diameter aluminum cap stamped: Sec. cor., S-23, S-24, S-25, T47N, R42W, 1990, R.L.S. 28410. Bearing trees: 10" ash - N09°W - 10.24 feet
 10" ash - S83°E - 6.46 feet
 5" maple - S80°W - 10.56 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found my 2" iron pipe with a 4" diameter aluminum cap with the bearing trees in good condition as described above in Section "A". I updated this position to state and county specifications as noted below.

Act 74 record on file with Register of Deeds office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a 2" x 30" iron pipe with a 4" diameter aluminum cap as described above in Section "A". I established the following bearing trees and/or reference object:

- 10" ash - N09°W - 10.24 feet
- 10" ash - S83°E - 6.46 feet
- 5" maple - S80°W - 10.56 feet
- 6" steel rail with sign - due south - 2.00 feet

PEER GROUP APPROVED
Richard L. Decker 11/6/95
 COUNTY REPRESENTATIVE



Signed by John R. Garske Date 11-6-95
 Surveyor's Michigan License No. 28410