

SURVEY & REMONUMENTATION

JUN 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
26TH day of JANUARY
A. D. 1995 at 10:55 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 182

Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: Corner Code #

1. Public Land Survey Section 36	T <u>47N</u> R <u>42W</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1/4 corner to Sections 1 and 36, T47-46N, R42W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on November 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner by William Burt, Deputy Surveyor, August 6, 1847. Original bearing trees:
Cedar 8" - N67°E - 4 links Hemlock 14" - N37°W - 79 links

1981 - Richard Drahn, RLS 21564, set a 2" I.D. x 4 ft. long iron pipe with a 3" diameter brass cap stamped to identify the corner. Bearing trees he established:

6" R. maple - N32°W - 48.10 feet 8" hemlock - S82°E - 8.70 feet
5" Y. birch - S03°W - 39.75 feet Steel sign post - N76°W - 2.25 feet

Corner recorded 3/10/82, Liber 2, pg. 212.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument set by Dick Drahn in 1981 in good condition, the bearing trees are in good condition with the exception of the hemlock which is now a windfall. I established new accessories as noted below.

County record research on file with Register of Deeds.

PEER GROUP

Approved

Richard P. Drahn 1/25/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 2" I.D. x 4 ft. long concrete filled galvanized iron pipe with a 3" diameter brass cap stamped: T46-47N, R42W; 1/4; S-1; S-36; RLS 21564, from which I established the following bearing trees and/or reference objects:

8" R. maple - N23°W - 28.11 feet 6" Y. birch - S07°W - 39.84 feet
5" ash - N59°E - 27.11 feet Steel sign post - N69°W - 2.24 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 1-25-95

