

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Gogebic COUNTY
T 47N R 42W


DESCRIPTION OF CORNER Southeast corner of Govt. Lot 2, Section 21

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap, stamped **SOUTHEAST CORNER**

DATE MONUMENT PLACED AND WITNESSED July 20, 1971

**GOVT. LOT 2
SEC. 21
T47N, R42W**

WITNESSES TO CORNER..... Hemlock 7 S30°E (mag.) 10.4 ft. "BT"



Hemlock 8 N33°E (mag.) 11.1 ft. "BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.

Corner established at intersection of N&S 1/4 line, which is parallel with the west line of Sec. 21, and the S 1/16 line, which is parallel with the south line of Sec. 21. Found a 1" iron pin S39 $\frac{1}{2}$ °E 111.1 ft., probably a property corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE June 8, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68