

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER N'y terminus of E boundary of L. Gogebic State Park

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 20, 1971

WITNESSES TO CORNER..... Cedar 10 N54^oW (mag.) 34.3 ft. "BT"



Sugar Maple 12 N86^oW (mag.) 26.3 ft. "BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument marks the direction of the east boundary of Lake Gogebic State Park, and is set near the water's edge of Lake Gogebic at a point 1028.1 feet N'y of a monument at the southeast corner of Lake Gogebic State Park, said monument being 330.0 feet W'y of the SE corner of Govt. Lot 2, Sec. 21, T47N, R42W. East boundary of the park terminates at the water's edge of Lake Gogebic, and is parallel with West line of Section 21.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE June 8, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68