


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Gogebic COUNTY
T 47N R 42N

DESCRIPTION OF CORNER Southeast corner of Govt. Lot 3, Section 21
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap, stamped
DATE MONUMENT PLACED AND WITNESSED July 20, 1971
WITNESSES TO CORNER..... Hemlock 16 S40°W (mag.) 37.5 ft. "1/16S, BT"

SOUTHEAST CORNER
GOVT. LOT 3
Sec. 21
T47N, R42W



Yellow Birch 6 S88°W (mag.) 8.5 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously. Corner established at intersection of line parallel with west line of Sec. 21 and beginning at the W1/16 corner bet. Sec. 21 & 28, and a line parallel with south line of Sec. 21 and beginning at S 1/16 corner between Sec. 20 & 21.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE June 16, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68