

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER Center of SE $\frac{1}{4}$ of Section 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 14, 1971

WITNESSES TO CORNER..... Sugar Maple 6 S89 $^{\circ}$ E (mag.) 4.3 ft. "1/16S, BT"



Sugar Maple 4 N46 $^{\circ}$ W (mag.) 16.5 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.
Corner established on line between S 1/16 cor. bet. Sec. 20 & 21 and
S 1/16 cor. on N & S $\frac{1}{4}$ line of Sec. 20, at calculated intersection with
a line joining the E 1/16 cor. on E & W $\frac{1}{4}$ line of Sec. 20 and the E 1/16
cor. bet. Sec. 20 & 29; that is, at the calculated intersection of the
quarter-quarter section lines.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE June 20, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68