

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY  
T 47N R 42W

DESCRIPTION OF CORNER South 1/16 corner on N & S 1/4 line of Section 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 12, 1971

WITNESSES TO CORNER..... Sugar Maple 6 N75°E (mag.) 3.3 ft. "1/16S, BT"



Sugar Maple 12 S22°E (mag.) 27.4 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.  
Corner established on line between Center 1/4 corner 1339.5 ft. N and  
South 1/4 corner 1339.5 ft. S.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE June 20, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68