

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER Center of Section 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 12, 1971

WITNESSES TO CORNER..... Cedar 8 S59°E (mag.) 16.9 ft. "1/4S, NBT"



Hemlock 12 N18°E (mag.) 16.3 ft. "1/4S, NBT"

Also squared and scribed a 6" hemlock N15°W
2.2 ft. from corner.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a squared wood post N13°44'W 77.2 ft. from true intersection of quarter lines, previously set for an approximate corner.

Corner established at intersection of quarter-section lines.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 20, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68