

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

✓


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER North 1/16 corner on N & S ¼ line of Section 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 12, 1971

WITNESSES TO CORNER..... Sugar Maple 14 N86°E (mag.) 14.9 ft. "1/16S, BT"



Hemlock 11 S50°E (mag.) 22.7 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.
Corner established on line between North 1/4 corner 1356.4 ft. N and
Center 1/4 corner 1356.4 ft. S.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 20, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68