

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Gogebic COUNTY
T 47N R 42W

DESCRIPTION OF CORNER East 1/16 corner between Sections 17 and 20

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 12, 1971

WITNESSES TO CORNER..... Cedar 8 N87°W (mag.) 15.3 ft. "1/16S, BT"



Cedar 10 N68°E (mag.) 8.7 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established proportionately on line between 1/4 corner 1313.0 ft. W and meander corner (Manning Plat corner) 1173.7 ft. E. Corner is in an old sanitary land fill, which may have buried any prior existing corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68